




February 16, 2012

Judith Enck, Regional Coordinator
U.S. Environmental Protection Agency-Region 2
290 Broadway Avenue
New York, NY 10007-1866



Re: Notification of Proposed PCB Remediation Activities
Braddock Frosted Foods Property
Braddock Avenue and Bailey Lane
Block 5805, Lots 2 and 4
Winslow Township
Camden County, New Jersey
NJDEP Case Number: 08-06-25-1339-41
NJDEP Program Interest Number: 489315

Dear Regional Coordinator,

Northstar Environmental Services (NES) submits this written notification of proposed polychlorinated biphenyl (PCB) remediation activities for the above-referenced site (the "Site") on behalf of the current property owner, Braddock Frosted Foods, Inc. Remedial activities at the Site have proceeded to date under the oversight of the New Jersey Department of Environmental Protection ("NJDEP"), and have included the collection of a total of one hundred seventy-nine (179) soil samples from the 13.78 acre Site to investigate PCB-impacted soil. Of those samples, only one isolated sample location – designated as SB-36 - exhibited concentrations of PCBs greater than 50 mg/kg. That one location was later resampled and the results of that sampling were less than 50 mg/kg.

Based on the detailed sampling to date, NES submitted a Remedial Action Workplan to NJDEP outlining a proposed remedial approach to address PCB-impacted soil at the Site that includes excavation and off-site disposal of all PCB-impacted soil exceeding the New Jersey Non-Residential Direct Contact Soil Remediation Standard (NRDCSRS) of 1 mg/kg, which equates to the Toxic Substances Control Act ("TSCA") unrestricted use cleanup criteria of 1 ppm. The NJDEP Case Manager verbally approved our proposed remedial approach with the stipulation that NES notify USEPA regarding the remediation and disposal of any isolated hazardous PCB-impacted soil associated with soil sample SB-36, which would be confined to Remediation Area D1 in the attached Figure 3. NJDEP also requested that NES collect an additional soil sample from Remediation Area D1 for horizontal delineation purposes.

This notification presents a summary of pertinent background information pertaining to previous investigation activities and includes a narrative description of the proposed remediation strategy to address PCBs identified in soil at the Site (designated as Area of Concern AOC-1).

1.0 Background

PCB impact was identified during Site Investigation (SI), Emergency Response, Supplemental SI and Remedial Investigation (RI) activities, which were previously conducted at the Site. SI, Emergency Response and Supplemental SI activities were performed beginning in 2008 under NJDEP Case Number 08-06-25-1339-41 in response to a suspected discharge of dielectric fluid from pole-mounted transformers formerly present at the Site. RT Environmental Services, Inc., the environmental consultant working on the investigation at that time, contacted EPA Region II, provided a summary of the investigation, and was directed by EPA to proceed under the oversight of NJDEP.

Based upon the RI activities completed to date, it appears unlikely that an isolated transformer discharge could have been the source of the distributed PCB impacts at the Site. The demolition of the former Braddock Frosted Foods Facility is thought to be a possible source of the PCB impacts, but this cannot be confirmed.

Based on the results of investigations completed to date, the selected remedial standard for the Site is the New Jersey NRDCSRS of 1 mg/kg, which sets the same cleanup criteria as the TSCA unrestricted use cleanup criteria of 1 ppm. The proposed remedial strategy includes excavation and off-site disposal of PCB-contaminated soil exceeding the NJ NRDCSRS (and the TSCA unrestricted use cleanup criteria) of 1 mg/kg. This includes an estimated 2,224 tons of non-hazardous PCB-impacted soils (e.g. Remediation Areas A, B, C, D2, E, F1, F2 and F3), and an estimated 130 tons of soil from Remediation Area D1 that NES plans to handle as hazardous as a precautionary measure even though the hazardous or non-hazardous nature of that soil has not been confirmed at this time. Following completion of the selected remedial action, a deed notice will be prepared for the Site pursuant to the NJDEP Technical Requirements for Site Remediation, N.J.A.C. 7:26E. The deed notice will be prepared to address PCBs proposed to remain in soil at the Site at concentrations below the NJDEP NRDCSRS of 1 ppm, but exceeding the NJDEP Residential Direct Contact Soil Remediation Standard (RDCSRS) of 0.2 ppm.

Previous investigation activities were documented in NES's December 2010 Remedial Investigation Workplan, June 2011 Remedial Investigation Report and October 2011 Remedial Action Workplan, which were submitted to NJDEP. NES continues to coordinate remediation efforts with NJDEP.

2.0 Applicability

As noted above, one of the one-hundred and seventy-nine (179) soil samples taken at the Site reported concentrations of PCBs greater than 50 ppm, with the remaining samples all reporting concentrations at or below 16 ppm. The one sample, designated as SB-36, reported PCB concentrations of 160 ppm, a level that is an order of magnitude greater than any other sample results at the Site, including a prior sample (S-24C) taken immediately adjacent to the location of SB-36 that reported a PCB concentration of 16 ppm. A subsequent sample taken at the location

of SB-36 at an interval depth of 1.5-2.0' (S-61) was unable to confirm the concentrations reported in sample SB-36 and also reported a concentration of 16 ppm. As a result, despite extensive sampling, there has been no confirmed evidence that the source of the PCB impacts at the Site exceeded 50 ppm.

While the source of PCBs at the Site, as well as the date and PCB concentration of any such discharge remain unconfirmed, Braddock Frosted Foods is proceeding with this notification under 40 CFR 761.61(a) and is planning to conduct a self-implementing cleanup for purposes of the remediation of any PCB-impacted soil in the area surrounding SB-36 and designated as Area D1. The self-implementing procedures applicable to this Site are limited to addressing PCB-impacted soil.

3.0 Site Characterization

To date, NES has collected a total of one hundred seventy-nine (179) soil samples to investigate PCB-impacted soil at AOC-1. Based on the results of RI activities completed to date, the limit of PCB-impacted soil associated with Remediation Areas A, B, C, D2, E, and F1 has been horizontally and vertically delineated. The PCB-impacted soil associated with Remediation Areas D1, F2 and F3 has been estimated and will be further evaluated during remedial action activities.

PCB impact has been vertically delineated by subsurface soil samples S-1A, PE-7D, B-1, B-2, B-3, SB-59A, SB-60, SB-61A, SB-62 and SB-64 collected across AOC-1. These samples were collected from depths ranging from the 1.5' to 2.0' depth interval to the 2.5' to 3.0' depth interval. The extent of PCB impact associated with each of the remediation areas is discussed below.

- *Remediation Area A* - The extent of PCB-impacted soil associated with Area A has been horizontally delineated by surface soil samples SB-3, SB-42, SB-44, SB-5, SB-6, S-29A, DS-1 and S-29C. Area A is approximately 2,525 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 3.0 feet bgs.
- *Remediation Area B* - The extent of PCB-impacted soil associated with Area B has been horizontally delineated by surface soil samples S-18, S17D, S-16C, S-16D and PE-8B. Area B is approximately 253 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 2.0 feet bgs.
- *Remediation Area C* - The extent of PCB-impacted soil associated with Area C has been horizontally delineated by surface soil samples PE-9C, S-12, S-2, S-1 and S-7. Area C is approximately 349 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 2.0 feet bgs.

- *Remediation Area D1* – The extent of PCB-impacted soil associated with Area D1 has been horizontally delineated by surface soil samples S-26B, PE-7, PE-10B, S-24A, S-24D and S-26A. Area D1 is estimated to be approximately 780 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 3.0 feet bgs. The NJDEP Case Manager verbally approved the proposed utilization of existing data collected during the RI in lieu of collection of post-excavation soil samples in areas where PCBs are both horizontally and vertically delineated. Pursuant to the NJDEP Technical Requirements for Site Remediation, N.J.A.C. 7:26E, post-excavation sidewall samples should be collected at a frequency of one sample per thirty (30) linear feet. Therefore, NJDEP is requiring that an additional soil sample be collected from Remediation Area D1 between samples S-26B and PE-7/7D, which are separated by a distance greater than forty (40) feet. Based on the required sampling frequency, NES will collect one (1) additional soil sample from the proposed northwestern sidewall between soil sample locations S-26B and PE-7/7D to satisfy the post-excavation sampling frequency and verify horizontal delineation. The soil sample will be submitted under executed chain-of-custody to a New Jersey certified laboratory for PCBs analysis. NES anticipates that the horizontal limit of Remediation Area D1 will not change.
- *Remediation Area D2* - The extent of PCB-impacted soil associated with Area D2 has been horizontally delineated by surface soil samples S-26A, S-24D, S-24A, PE-10B, PE-7, PE-10, S-15, S-22, S-22C and SB-31. Area D2 is approximately 956 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 3.0 feet bgs.
- *Remediation Area E* - The extent of PCB-impacted soil associated with Area E has been horizontally delineated by surface soil samples DS-3, DS-2, S-18C, S19 and S-19C. Area E is approximately 549 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 2.0 feet bgs.
- *Remediation Area F1* - The extent of PCB-impacted soil associated with Area F1 has been horizontally delineated by surface soil samples SB-46, SB-55, SB-56, SB-48, SB-49, SB-50, SB-10, S-36A, S-36D, S-32B, S-32A, SB21, SB-20 and SB-17. Area F1 is approximately 7,318 square feet and PCB impacts in the area have been vertically delineated to extend to a depth of 2.0 feet bgs.
- *Remediation Area F2* – The extent of PCB-impacted soil associated with Area F2 has been horizontally delineated by surface soil samples SB-18, S-33B, S-33, S-33D and SB-20. The vertical limit of PCB impact was not determined at subsurface soil sample location SB-63A (2.9 mg/kg), which is located within Area F2. Area F2 is approximately 516 square feet and PCB impacts in the area extend to an estimated depth of 4.0 feet bgs.

- *Remediation Area F3* – The extent of PCB-impacted soil associated with Area F3 has been horizontally delineated to the south by surface soil samples DS-4, SB-56, SB-55, SB-46 and DS-6. The horizontal extent of PCB impact has not be defined to the north, east or west of soil sample SB-54 (12 mg/kg). Area F3 has been estimated to be approximately 1,098 square feet based upon current sample results and PCB impacts in the area have been vertically delineated to extend to an estimated depth of 3.0 feet bgs.

Sampling and investigation activities were performed in accordance with the NJDEP Technical Requirements for Site Remediation, the NJDEP Field Sampling Procedures Manual (August 2005) and, where applicable, portions United States Environmental Protection Agency (USEPA) regulations and guidance for conducting investigations. NES consulted USEPA's *Subpart N—Cleanup Site Characterization Sampling for PCB Remediation Waste in Accordance with §761.61(a)(2)* to assess the sufficiency of existing Site characterization analytical data.

Samples were packaged on ice to maintain 4 degrees Celsius immediately after collection. Each sample was analyzed at a New Jersey-certified analytical laboratory for PCBs using EPA's analytical method SW-846 consistent with Table 2.1 of the NJDEP Technical Requirements for Site Remediation and USEPA Subpart N. All soil sample concentrations for PCBs were reported on a dry weight basis as milligrams of PCBs per kilogram of sample.

Figure 1 presents the Site on a copy of the United States Geological Survey (USGS) 7.5-minute topographic map (Williamstown Quadrangle). **Figure 2** depicts the Site on a 2009 aerial photograph utilizing New Jersey Geographic Information System aerial imagery. **Figure 3** depicts the PCB impact area (AOC-1) at the Site on the Existing Topographic Survey Conditions Plan prepared by Remington & Vernick Engineers dated March 11, 2010. Analytical results for soil samples collected from AOC-1 are provided in tabular format on Figure 3.

4.0 Notification and Certification Requirements

NES is providing notification at least 30 days prior to the anticipated start date for Site remediation activities. Written notification has been provided to the USEPA Regional Administrator, the NJDEP Commissioner (ATTN: NJDEP Case Manager Cheryl Priest), and the Winslow Township Municipal Clerk.

A written certification, signed by the owner of the property where the cleanup Site is located and the party conducting the cleanup, has been prepared and included as an attachment to this notification.

5.0 Site Cleanup

The intended Remedial Action includes excavation and off-site disposal of PCB-impacted soil exceeding the NJ NRDCSRS of 1 mg/kg, which sets the same cleanup criteria as the TSCA

unrestricted use cleanup criteria of 1 ppm. While New Jersey requirements will mandate the implementation of a Deed Restriction restricting the Site to non-residential use, construction of a cap and implementation of a Deed Restriction to meet USEPA requirements will not be necessary.

PCB-impacted soil associated with Areas A, B, C, D1, D2, E, F1, F2 and F3 will be excavated and disposed off-site. The anticipated duration of the proposed remedial actions is approximately four months. This includes anticipated field activities and reporting. NES anticipates thirteen (13) field days will be required to complete the following Site activities:

- Equipment mobilization;
- Collection of waste classification samples;
- Survey and staking of remediation areas;
- Vegetation clearing;
- Soil excavation;
- Post-excavation soil sampling;
- Soil transportation and disposal; and
- Site Restoration.

NES estimates a total of 2,224-tons of non-hazardous soil will be excavated from Remediation Areas A, B, C, D2, E, F1, F2 and F3. NES estimates that a total of 130 tons of soil will be excavated from Remediation Area D1, which NES plans to handle as hazardous as a precautionary measure even though there has been no confirmation to date that the soil in this area will indeed be hazardous. Soil will be excavated using a track excavator and loader and staged at an area designated for subsequent loading. The soil will then be loaded and transported under manifest to an appropriate disposal facility.

Soils excavated from the Site will be transported off-site for disposal in containers meeting the requirements of the DOT Hazardous Materials Regulations (HMR) at 49 CFR parts 171 through 180. Soils excavated from Area D1 will be disposed of in a hazardous waste landfill permitted by EPA under section 3004 of RCRA, or by a State authorized under section 3006 of RCRA, or an approved PCB disposal facility. The generator will provide written notice, including the quantity to be shipped and highest concentration of PCBs at least 15 days prior to the first shipment of bulk PCB remediation waste from the Site, to the off-site facility where the waste is destined.

The excavation limits for each of the proposed Remediation Areas is presented on **Figure 3**.

6.0 Cleanup Verification

Consistent with 40 CFR §761.61(a) (6), Subpart O, post-cleanup verification sampling will be conducted in Remediation Area D1 in order to confirm that the TSCA unrestricted use cleanup

February 16, 2012
Page 7

standard has been met. Remediation Area D1 is estimated to be approximately 780 square feet in size. Using the 1.5 meter sampling grid outlined in Subpart O, eight (8) composite sampling areas are located within the remediation area and NES will collect eight (8) composite samples for PCBs analysis from the area. The soil samples will be submitted under an executed chain-of-custody to a New Jersey certified laboratory. Proposed sample compositing areas are depicted on **Figure 4**.

Should you have any questions concerning this notification, please do not hesitate to contact me at pdeblasio@nstarenvironmental.com or at 609.263.6666.

Very truly yours,

NORTHSTAR ENVIRONMENTAL SERVICES





Paul DeBlasio
General Manager
USO1235/188226

Attachments: A) Figures
B) Tables
C) Owner Certification

cc: USEPA Section Chief-Region 2 (ATTN: Henry Mazzucca)
NJDEP Commissioner Robert Martin (ATTN: NJDEP Case Mgr. Cheryl Priest)
Municipal Clerk, Winslow Township
Christopher Ball, Esq., Manko, Gold, Katcher & Fox LLP

2012 FEB 23 AM 7:55
EPA REGION 2
CORRESPONDENCE
CONTROL OFFICE



THIS MAP IS BASED ON USGS 7.5
MINUTE WILLIAMSTOWN NJ
TOPOGRAPHIC MAP DATED 1981

LEGEND:

- 1 MILE RADIUS
- SITE LOCATION

**BRADDOCK FROSTED FOODS PROPERTY
BRADDOCK AVE. & BAILEY LANE
WINSLOW TOWNSHIP
CAMDEN COUNTY
NEW JERSEY**


FIGURE 1

USGS TOPOGRAPHIC MAP

**NORTHSTAR
★ ENVIRONMENTAL
SERVICES**

**36 CLERMONT DRIVE
CLERMONT, NJ 08210
(609) 263 - 6666
FAX (609) 624 - 1055**

SCALE:	DATE:	DRAWN BY:	DES. BY:	FILE NO.	CHK. BY:
1"=2000'	03/06/10	WG	MAG	112	WG



0 150 300 FEET

SCALE

THIS MAP IS BASED ON GOOGLE
AERIAL IMAGERY DATED 2009

LEGEND:



SITE LOCATION

BRADDOCK FROSTED FOODS PROPERTY
BRADDOCK AVE. & BAILEY LANE
WINSLOW TOWNSHIP
CAMDEN COUNTY
NEW JERSEY

FIGURE 2 AERIAL LOCATION MAP

NORTHSTAR
★ **ENVIRONMENTAL**
SERVICES

36 CLERMONT DRIVE
CLERMONT, NJ 08210
(609) 263 - 6666
FAX (609) 624 - 1055

SCALE:

1" = 300'

DATE:

03/06/10

DRAWN
BY:

WG

DES. BY

MAG

FILE NO.

112

CHK. BY:

WG

Table 1: December 12, 2008 Site Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S1		S1A		S2		S3		S4		S5		S6		S7		S8	
Sample ID				AC41760-001		AC41760-016		AC41760-002		AC41760-003		AC41760-004		AC41760-005		AC41760-006		AC41760-007		AC41760-008	
Sample Date				0.0-0.5'		2.0-2.5		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'	
Sample Depth				12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008	
Sample Matrix				SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBs																					
Aroclor (Total)	0.2	1	0.2	0.52	0.032	ND	0.028	0.35	0.028	ND	0.028	ND	0.028	ND	0.027	1.4	0.034	0.63	0.031	0.12	0.03
Aroclor-1016	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	ND	0.03
Aroclor-1221	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	ND	0.03
Aroclor-1232	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	ND	0.03
Aroclor-1242	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	ND	0.03
Aroclor-1248	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	0.26	0.034	0.19	0.031	ND	0.03
Aroclor-1254	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	0.12	0.03
Aroclor-1260	0.2	1	0.2	0.52	0.032	ND	0.028	0.35	0.028	ND	0.028	ND	0.028	ND	0.027	1.1	0.034	0.44	0.031	ND	0.03
Aroclor-1262	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	ND	0.03
Aroclor-1268	0.2	1	0.2	ND	0.032	ND	0.028	ND	0.028	ND	0.028	ND	0.028	ND	0.027	ND	0.034	ND	0.031	ND	0.03
Diesel Range Organics	5100	5100	5100	2000	230	ND	67	4700	340	ND	67	ND	67	ND	66	13000	810	1400	74	100	72

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 1: December 12, 2008 Site Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S9		S10		S11		S12		S13		S14		S15	
Sample ID				AC41760-009		AC41760-010		AC41760-011		AC41760-012		AC41760-013		AC41760-014		AC41760-015	
Sample Date				0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'	
Sample Depth				12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008		12/12/2008	
Sample Matrix				SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBs																	
Aroclor (Total)	0.2	1	0.2	ND	0.028	0.18	0.041	0.33	0.032	0.51	0.037	ND	0.029	0.18	0.03	0.33	0.032
Aroclor-1016	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	ND	0.037	ND	0.029	ND	0.03	ND	0.032
Aroclor-1221	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	ND	0.037	ND	0.029	ND	0.03	ND	0.032
Aroclor-1232	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	ND	0.037	ND	0.029	ND	0.03	ND	0.032
Aroclor-1242	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	ND	0.037	ND	0.029	ND	0.03	ND	0.032
Aroclor-1248	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	0.14	0.037	ND	0.029	0.046	0.03	ND	0.032
Aroclor-1254	0.2	1	0.2	ND	0.028	0.18	0.041	0.33	0.032	ND	0.037	ND	0.029	ND	0.03	0.33	0.032
Aroclor-1260	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	0.37	0.037	ND	0.029	0.13	0.03	ND	0.032
Aroclor-1262	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	ND	0.037	ND	0.029	ND	0.03	ND	0.032
Aroclor-1268	0.2	1	0.2	ND	0.028	ND	0.041	ND	0.032	ND	0.037	ND	0.029	ND	0.03	ND	0.032
Diesel Range Organics	5100	5100	5100	ND	67	ND	98	110	76	740	88	ND	71	700	72	ND	77

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 2: February 25, 2009 Remedial Action Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	PE1		PE2		PE3		PE4		PE5		PE6		PE7		PE7D		PE8		PE9	
Sample ID				AC42996-001		AC42996-002		AC42996-003		AC42996-004		AC42996-005		AC42996-006		AC42996-007		AC42996-011		AC42996-008		AC42996-009	
Sample Date				2/25/2009		2/25/2009		2/25/2009		2/25/2009		2/25/2009		2/25/2009		2/25/2009		2/25/2009		2/25/2009		2/25/2009	
Sample Depth				0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5		0.0-0.5	
Sample Matrix				SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL		SOIL	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBS																							
Aroclor (Total)	0.2	1	0.2	ND	0.027	ND	0.027	0.069	0.028	0.085	0.026	0.037	0.027	0.076	0.028	ND	0.027	ND	0.027	0.38	0.028	0.22	0.028
Aroclor-1016	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1221	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1232	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1242	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1248	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1254	0.2	1	0.2	ND	0.027	ND	0.027	0.069	0.028	ND	0.026	ND	0.027	0.076	0.028	ND	0.027	ND	0.027	0.38	0.028	0.22	0.028
Aroclor-1260	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	0.085	0.026	0.037	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1262	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Aroclor-1268	0.2	1	0.2	ND	0.027	ND	0.027	ND	0.028	ND	0.026	ND	0.027	ND	0.028	ND	0.027	ND	0.027	ND	0.028	ND	0.028
Diesel Range Organics	5100	5100	5100	ND	66	ND	65	ND	67	ND	63	410	64	ND	67	ND	65	ND	65	ND	67	95	67

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 2: February 25, 2009 Remedial Action Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	PE10		B1		B2		B3	
Sample ID				AC42996-010		AC42996-012		AC42996-013		AC42996-014	
Sample Date				2/25/2009		2/25/2009		2/25/2009		2/25/2009	
Sample Depth				0.0-0.5		2.0-2.5		2.0-2.5		2.0-2.5	
Sample Matrix				SOIL		SOIL		SOIL		SOIL	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL
PCBS											
Aroclor (Total)	0.2	1	0.2	0.32	0.03	0.062	0.027	ND	0.027	0.097	0.027
Aroclor-1016	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1221	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1232	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1242	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1248	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1254	0.2	1	0.2	0.32	0.030	0.062	0.027	ND	0.027	0.097	0.027
Aroclor-1260	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1262	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Aroclor-1268	0.2	1	0.2	ND	0.030	ND	0.027	ND	0.027	ND	0.027
Diesel Range Organics	5100	5100	5100	ND	72	ND	65	66	65	ND	66

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 3: May 14, 2009 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S16		S17		S18		S19		S20		S21		S22		S23		S24	
Sample ID				AC44648-001		AC44648-002		AC44648-003		AC44648-004		AC44648-005		AC44648-006		AC44648-007		AC44648-008		AC44648-009	
Sample Date				5/14/2009		5/14/2009		5/14/2009		5/14/2009		5/14/2009		5/14/2009		5/14/2009		5/14/2009		5/14/2009	
Sample Depth				0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'	
Sample Matrix				Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBS																					
Aroclor (Total)	0.2	1	NA	0.23	0.032	0.21	0.031	0.41	0.032	0.9	0.028	0.63	0.037	0.067	0.026	0.22	0.033	ND	0.03	7.7	0.32
Aroclor-1016	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1221	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1232	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1242	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1248	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1254	0.2	1	0.2	0.23	0.032	0.21	0.031	0.41	0.032	0.90	0.028	0.63	0.037	0.067	0.026	0.22	0.033	ND	0.030	7.7	0.32
Aroclor-1260	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1262	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Aroclor-1268	0.2	1	0.2	ND	0.032	ND	0.031	ND	0.032	ND	0.028	ND	0.037	ND	0.026	ND	0.033	ND	0.030	ND	0.32
Diesel Range Organics	5100	5100	5100	ND	78	120	74	ND	77	79	68	150	88	ND	62	ND	80	ND	73	ND	76

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight indicates an Exceedence of the Applicable Standard

Table 4: September 30, 2009 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S24A		S25		S26		S28		S29		S30		S31		S32		S33		S34	
Sample ID				AC47421-001		AC47421-002		AC47421-003		AC47421-004		AC47421-005		AC47421-006		AC47421-007		AC47421-008		AC47421-009		AC47421-010	
Sample Date				9/30/2009		9/30/2009		9/30/2009		9/30/2009		9/30/2009		9/30/2009		9/30/2009		9/30/2009		9/30/2009		9/30/2009	
Sample Depth				0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'		0.0-05'	
Sample Matrix				Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBS																							
Aroclor (Total)	0.2	1	NA	0.11	0.032	0.14	0.039	0.21	0.036	0.15	0.038	0.91	0.037	0.53	0.032	ND	0.029	1.8	0.037	0.99	0.037	1.5	0.035
Aroclor-1016	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1221	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1232	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1242	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1248	0.2	1	0.2	ND	0.032	0.14	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1254	0.2	1	0.2	0.11	0.032	ND	0.039	0.21	0.036	0.15	0.038	0.91	0.037	0.53	0.032	ND	0.029	1.8	0.037	0.99	0.037	1.5	0.035
Aroclor-1260	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1262	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Aroclor-1268	0.2	1	0.2	ND	0.032	ND	0.039	ND	0.036	ND	0.038	ND	0.037	ND	0.032	ND	0.029	ND	0.037	ND	0.037	ND	0.035
Diesel Range Organics	5100	5100	5100	NS		NS		NS		NS		NS		NS		NS		NS		NS		NS	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 4: September 30, 2009 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S35		S36		BK-1	
Sample ID				AC47421-011		AC47421-012		AC47421-013	
Sample Date				9/30/2009		9/30/2009		9/30/2009	
Sample Depth				0.0-05'		0.0-05'		0.0-05'	
Sample Matrix				Soil		Soil		Soil	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL
PCBS									
Aroclor (Total)	0.2	1	NA	ND	0.043	ND	0.043	ND	0.027
Aroclor-1016	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1221	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1232	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1242	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1248	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1254	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1260	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1262	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Aroclor-1268	0.2	1	0.2	ND	0.043	ND	0.043	ND	0.027
Diesel Range Organics	5100	5100	5100	NS		NS		NS	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceednce of the Applicable Standard

Table 5: Summary of Analytical Methods and Quality Assurance Indicators
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Sample Matrix Type	Samples per Matrix	Trip Blanks	Field Blanks	Duplicates	Analytical Parameter	Analytical Methods	Sample Preservation	Sample Container Volume and Type	Sample Holding Time
Soil	117	0	0	4	PCBs	8082	Ice (4°C)	8 oz. Glass	14 Days
	6	0	0	0	PCBs/SPLP PCBs	8082	Ice (4°C)	8 oz. Glass	14 Days

Notes:

PCBs Polychlorinated Biphenyls
 SPLP Synthetic Precipitation Leaching Procedure
 °C Degrees centigrade
 oz. Ounce

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL		PE-8A				PE-8B				PE-8C				PE-9A				PE-9B				PE-9C			
Sample ID					460-11823-1				460-11823-2				460-11823-3				460-11823-4				460-11823-5				460-11823-6			
Sample Date					4/1/10				4/1/10				4/1/10				4/1/10				4/1/10				4/1/10			
Sample Depth					0.0-0.5'				0.0-0.5'				0.0-0.5'				0.0-0.5'				0.0-0.5'				0.0-0.5'			
Sample Matrix					Soil				Soil				Soil				Soil				Soil				Soil			
Dilution Factor					1				1				1				1				1				1			
Parameter (mg/kg)																												
PCBs					MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q			
Aroclor 1016	0.20	1.0	0.20	0.017	0.091	U	0.016	0.084	U	0.016	0.083	U	0.016	0.082	U	0.016	0.082	U	0.015	0.076	U							
Aroclor 1221	0.20	1.0	0.20	0.027	0.091	U	0.025	0.084	U	0.025	0.083	U	0.025	0.082	U	0.025	0.082	U	0.023	0.076	U							
Aroclor 1232	0.20	1.0	0.20	0.051	0.091	U	0.047	0.084	U	0.047	0.083	U	0.046	0.082	U	0.046	0.082	U	0.043	0.076	U							
Aroclor 1242	0.20	1.0	0.20	0.017	0.091	U	0.016	0.084	U	0.016	0.083	U	0.016	0.082	U	0.015	0.082	U	0.014	0.076	U							
Aroclor 1248	0.20	1.0	0.20	0.024	0.091	U	0.022	0.084	U	0.022	0.083	U	0.022	0.082	U	0.022	0.082	U	0.020	0.076	U							
Aroclor 1254	0.20	1.0	0.20	0.031	0.24		0.029	0.87		0.028	0.71		0.028	0.49		0.028	0.13		0.026	0.076	U							
Aroclor 1260	0.20	1.0	0.20	0.010	0.091	U	0.0093	0.084	U	0.0093	0.083	U	0.0091	0.082	U	0.0091	0.13		0.0085	0.076	U							
Aroclor 1262	NA	NA	NA	0.016	0.091	U	0.014	0.084	U	0.014	0.083	U	0.014	0.082	U	0.014	0.082	U	0.013	0.076	U							
Aroclor 1268	NA	NA	NA	0.016	0.091	U	0.014	0.084	U	0.014	0.083	U	0.014	0.082	U	0.014	0.082	U	0.013	0.076	U							
Percent Solids (%)	NA	NA	NA	1.0	73.9		1.0	80.0		1.0	80.3		1.0	81.6		1.0	82.0		1.0	87.9								

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	PE-10A			PE-10B			PE-10C			S-16A			S-16B			S-16C		
Sample ID				460-11823-7			460-11823-8			460-11823-9			460-11823-10			460-11823-11			460-11823-12		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			5			5			1			1			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.016	0.081	U	0.089	0.47	U	0.089	0.47	U	0.016	0.086	U	0.018	0.092	U	0.018	0.094	U
Aroclor 1221	0.20	1.0	0.20	0.025	0.081	U	0.14	0.47	U	0.14	0.47	U	0.026	0.086	U	0.028	0.092	U	0.028	0.094	U
Aroclor 1232	0.20	1.0	0.20	0.046	0.081	U	0.27	0.47	U	0.26	0.47	U	0.049	0.086	U	0.052	0.092	U	0.053	0.094	U
Aroclor 1242	0.20	1.0	0.20	0.015	0.081	U	0.089	0.47	U	0.088	0.47	U	0.016	0.086	U	0.018	0.092	U	0.018	0.094	U
Aroclor 1248	0.20	1.0	0.20	0.022	0.081	U	0.12	5.0		0.12	4.2		0.023	0.086	U	0.025	0.092	U	0.025	0.094	U
Aroclor 1254	0.20	1.0	0.20	0.028	0.29		0.16	0.47	U	0.16	0.47	U	0.029	0.51		0.032	0.092	U	0.032	0.085	J
Aroclor 1260	0.20	1.0	0.20	0.0091	0.081	U	0.052	0.47	U	0.052	0.47	U	0.0096	0.086	U	0.010	0.092	U	0.010	0.094	U
Aroclor 1262	NA	NA	NA	0.014	0.081	U	0.080	0.47	U	0.080	0.47	U	0.015	0.086	U	0.016	0.092	U	0.016	0.094	U
Aroclor 1268	NA	NA	NA	0.014	0.081	U	0.080	0.47	U	0.080	0.47	U	0.015	0.086	U	0.016	0.092	U	0.016	0.094	U
Percent Solids (%)	NA	NA	NA	1.0	82.2		1.0	71.5		1.0	72.0		1.0	77.7		1.0	72.4		1.0	71.0	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceednce of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-16D			S-17A			S-17B			S-17C			S-17D			S-18A		
Sample ID				460-11823-13			460-11823-14			460-11823-15			460-11823-16			460-11823-17			460-11823-18		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			1			1			1			1			2		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.017	0.091	U	0.017	0.089	U	0.019	0.10	U	0.019	0.098	U	0.017	0.087	U	0.034	0.18	U
Aroclor 1221	0.20	1.0	0.20	0.027	0.091	U	0.027	0.089	U	0.030	0.10	U	0.030	0.098	U	0.026	0.087	U	0.053	0.18	U
Aroclor 1232	0.20	1.0	0.20	0.052	0.091	U	0.051	0.089	U	0.057	0.10	U	0.056	0.098	U	0.049	0.087	U	0.10	0.18	U
Aroclor 1242	0.20	1.0	0.20	0.017	0.091	U	0.017	0.089	U	0.019	0.10	U	0.019	0.098	U	0.016	0.087	U	0.034	0.18	U
Aroclor 1248	0.20	1.0	0.20	0.024	0.091	U	0.024	0.089	U	0.027	0.10	U	0.026	0.098	U	0.023	0.087	U	0.047	2.6	
Aroclor 1254	0.20	1.0	0.20	0.031	0.19		0.030	0.066	J	0.035	0.20		0.034	0.095	J	0.030	0.19		0.060	0.18	U
Aroclor 1260	0.20	1.0	0.20	0.010	0.091	U	0.010	0.089	U	0.011	0.10	U	0.011	0.098	U	0.0097	0.087	U	0.020	0.18	U
Aroclor 1262	NA	NA	NA	0.016	0.091	U	0.015	0.089	U	0.017	0.10	U	0.017	0.098	U	0.015	0.087	U	0.030	0.18	U
Aroclor 1268	NA	NA	NA	0.016	0.091	U	0.015	0.089	U	0.017	0.10	U	0.017	0.098	U	0.015	0.087	U	0.030	0.18	U
Percent Solids (%)	NA	NA	NA	1.0	73.3		1.0	75.0		1.0	66.2		1.0	68.3		1.0	77.2		1.0	75.6	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceednce of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-18B			S-18C			S-18D			S-19A			S-19B			S-19C		
Sample ID				460-11823-19			460-11823-20			460-11823-21			460-11823-22			460-11823-23			460-11823-24		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			1			1			1			1			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	
Aroclor 1016	0.20	1.0	0.20	0.020	0.11	U	0.017	0.091	U	0.016	0.086	U	0.019	0.099	U	0.019	0.099	U	0.017	0.087	
Aroclor 1221	0.20	1.0	0.20	0.032	0.11	U	0.027	0.091	U	0.026	0.086	U	0.030	0.099	U	0.030	0.099	U	0.026	0.087	
Aroclor 1232	0.20	1.0	0.20	0.060	0.11	U	0.052	0.091	U	0.049	0.086	U	0.056	0.099	U	0.056	0.099	U	0.049	0.087	
Aroclor 1242	0.20	1.0	0.20	0.020	0.11	U	0.017	0.091	U	0.016	0.086	U	0.019	0.099	U	0.019	0.099	U	0.016	0.087	
Aroclor 1248	0.20	1.0	0.20	0.028	0.11	U	0.024	0.091	U	0.023	0.086	U	0.026	0.099	U	0.026	0.099	U	0.023	0.087	
Aroclor 1254	0.20	1.0	0.20	0.036	0.86		0.031	0.22	p	0.029	0.52		0.034	0.99		0.034	1.5		0.030	0.25	
Aroclor 1260	0.20	1.0	0.20	0.012	0.11	U	0.010	0.091	U	0.0096	0.086	U	0.011	0.099	U	0.011	0.099	U	0.0097	0.087	
Aroclor 1262	NA	NA	NA	0.018	0.11	U	0.016	0.091	U	0.015	0.086	U	0.017	0.099	U	0.017	0.099	U	0.015	0.087	
Aroclor 1268	NA	NA	NA	0.018	0.11	U	0.016	0.091	U	0.015	0.086	U	0.017	0.099	U	0.017	0.099	U	0.015	0.087	
Percent Solids (%)	NA	NA	NA	1.0	63.1		1.0	73.2		1.0	77.8		1.0	67.8		1.0	67.3		1.0	77.2	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedance of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-19D			S-20A			S-20B			S-20C			S-20D			S-22A		
Sample ID				460-11823-25			460-11823-26			460-11823-27			460-11823-28			460-11823-29			460-11823-30		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			1			1			1			1			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.018	0.096	U	0.017	0.089	U	0.022	0.12	U	0.016	0.083	U	0.015	0.080	U	0.020	0.11	U
Aroclor 1221	0.20	1.0	0.20	0.029	0.096	U	0.027	0.089	U	0.035	0.12	U	0.025	0.083	U	0.024	0.080	U	0.032	0.11	U
Aroclor 1232	0.20	1.0	0.20	0.054	0.096	U	0.051	0.089	U	0.066	0.12	U	0.047	0.083	U	0.045	0.080	U	0.060	0.11	U
Aroclor 1242	0.20	1.0	0.20	0.018	0.096	U	0.017	0.089	U	0.022	0.12	U	0.016	0.083	U	0.015	0.080	U	0.020	0.11	U
Aroclor 1248	0.20	1.0	0.20	0.026	0.096	U	0.024	0.089	U	0.031	0.12	U	0.022	0.083	U	0.021	0.080	U	0.028	0.11	U
Aroclor 1254	0.20	1.0	0.20	0.033	0.47		0.030	0.42		0.039	0.47		0.028	0.53		0.027	0.56		0.036	0.11	U
Aroclor 1260	0.20	1.0	0.20	0.011	0.096	U	0.010	0.089	U	0.013	0.12	U	0.0093	0.083	U	0.009	0.080	U	0.012	0.11	U
Aroclor 1262	NA	NA	NA	0.016	0.096	U	0.015	0.089	U	0.020	0.12	U	0.014	0.083	U	0.014	0.080	U	0.018	0.11	U
Aroclor 1268	NA	NA	NA	0.016	0.096	U	0.015	0.089	U	0.020	0.12	U	0.014	0.083	U	0.014	0.080	U	0.018	0.11	U
Percent Solids (%)	NA	NA	NA	1.0	69.6		1.0	75.0		1.0	57.9		1.0	80.4		1.0	83.3		1.0	63.0	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceednce of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-22B			S-22C			S-22D			S-24A			S-24B			S-24C		
Sample ID				460-11823-31			460-11823-32			460-11823-33			460-11823-34			460-11823-35			460-11823-36		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				2			1			1			5			10			10		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.042	0.22	U	0.021	0.11	U	0.019	0.099	U	0.087	0.45	U	0.18	0.94	U	0.18	0.95	U
Aroclor 1221	0.20	1.0	0.20	0.066	0.22	U	0.033	0.11	U	0.030	0.099	U	0.14	0.45	U	0.28	0.94	U	0.29	0.95	U
Aroclor 1232	0.20	1.0	0.20	0.12	0.22	U	0.062	0.11	U	0.056	0.099	U	0.26	0.45	U	0.53	0.94	U	0.54	0.95	U
Aroclor 1242	0.20	1.0	0.20	0.041	0.22	U	0.021	0.11	U	0.019	0.099	U	0.086	0.45	U	0.18	0.94	U	0.18	0.95	U
Aroclor 1248	0.20	1.0	0.20	0.058	1.9		0.029	0.11	U	0.026	0.099	U	0.12	0.45	U	0.25	9.2		0.25	16	
Aroclor 1254	0.20	1.0	0.20	0.075	0.22	U	0.038	0.18		0.034	0.099	U	0.15	3.4		0.32	0.94	U	0.32	0.95	U
Aroclor 1260	0.20	1.0	0.20	0.024	0.22	U	0.012	0.11	U	0.011	0.099	U	0.051	0.45	U	0.10	0.94	U	0.11	0.95	U
Aroclor 1262	NA	NA	NA	0.037	0.22	U	0.019	0.11	U	0.017	0.099	U	0.078	0.45	U	0.16	0.94	U	0.16	0.95	U
Aroclor 1268	NA	NA	NA	0.037	0.22	U	0.019	0.11	U	0.017	0.099	U	0.078	0.45	U	0.16	0.94	U	0.16	0.95	U
Percent Solids (%)	NA	NA	NA	1.0	61.3		1.0	60.6		1.0	67.4		1.0	73.9		1.0	71.3		1.0	70.4	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-24D			S-26A			S-26B			S-26C			S-26D			S-29A		
Sample ID				460-11823-37			460-11823-38			460-11823-39			460-11823-40			460-11823-41			460-11823-42		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				2			1			1			1			1			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.036	0.19	U	0.018	0.096	U	0.018	0.094	U	0.025	0.13	U	0.018	0.095	U	0.018	0.095	U
Aroclor 1221	0.20	1.0	0.20	0.056	0.19	U	0.029	0.096	U	0.028	0.094	U	0.040	0.13	U	0.029	0.095	U	0.029	0.095	U
Aroclor 1232	0.20	1.0	0.20	0.11	0.19	U	0.054	0.096	U	0.053	0.094	U	0.074	0.13	U	0.054	0.095	U	0.054	0.095	U
Aroclor 1242	0.20	1.0	0.20	0.035	0.19	U	0.018	0.096	U	0.018	0.094	U	0.025	0.13	U	0.018	0.095	U	0.018	0.095	U
Aroclor 1248	0.20	1.0	0.20	0.050	2.3		0.025	0.096	U	0.025	0.094	U	0.035	0.13	U	0.025	0.095	U	0.025	0.095	U
Aroclor 1254	0.20	1.0	0.20	0.064	0.19	U	0.033	0.38		0.032	0.90		0.045	0.17		0.032	0.27		0.032	0.095	U
Aroclor 1260	0.20	1.0	0.20	0.021	0.19	U	0.011	0.096	U	0.011	0.094	U	0.015	0.13	U	0.011	0.095	U	0.011	0.095	U
Aroclor 1262	NA	NA	NA	0.032	0.19	U	0.016	0.096	U	0.016	0.094	U	0.023	0.13	U	0.016	0.095	U	0.016	0.095	U
Aroclor 1268	NA	NA	NA	0.032	0.19	U	0.016	0.096	U	0.016	0.094	U	0.023	0.13	U	0.016	0.095	U	0.016	0.095	U
Percent Solids (%)	NA	NA	NA	1.0	71.6		1.0	70.0		1.0	71.1		1.0	50.9		1.0	70.6		1.0	70.6	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-29B			S-29C			S-29D			S-30A			S-30B			S-30C		
Sample ID				460-11823-43			460-11823-44			460-11823-45			460-11823-46			460-11823-47			460-11823-48		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			1			1			1			1			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.018	0.093	U	0.018	0.096	U	0.019	0.097	U	0.021	0.11	U	0.017	0.086	U	0.017	0.092	U
Aroclor 1221	0.20	1.0	0.20	0.028	0.093	U	0.029	0.096	U	0.029	0.097	U	0.032	0.11	U	0.026	0.086	U	0.028	0.092	U
Aroclor 1232	0.20	1.0	0.20	0.053	0.093	U	0.055	0.096	U	0.055	0.097	U	0.061	0.11	U	0.049	0.086	U	0.052	0.092	U
Aroclor 1242	0.20	1.0	0.20	0.018	0.093	U	0.018	0.096	U	0.018	0.097	U	0.020	0.11	U	0.016	0.086	U	0.017	0.092	U
Aroclor 1248	0.20	1.0	0.20	0.025	0.89		0.026	0.66		0.026	1.4		0.029	0.14		0.023	0.16		0.024	0.12	
Aroclor 1254	0.20	1.0	0.20	0.032	0.093	U	0.033	0.096	U	0.033	0.097	U	0.037	0.31		0.030	0.37		0.031	0.19	
Aroclor 1260	0.20	1.0	0.20	0.010	0.093	U	0.011	0.096	U	0.011	0.097	U	0.012	0.11	U	0.0096	0.086	U	0.010	0.092	U
Aroclor 1262	NA	NA	NA	0.016	0.093	U	0.017	0.096	U	0.017	0.097	U	0.018	0.11	U	0.015	0.086	U	0.016	0.092	U
Aroclor 1268	NA	NA	NA	0.016	0.093	U	0.017	0.096	U	0.017	0.097	U	0.018	0.11	U	0.015	0.086	U	0.016	0.092	U
Percent Solids (%)	NA	NA	NA	1.0	72.3		1.0	69.3		1.0	69.0		1.0	62.2		1.0	77.3		1.0	73.2	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-30D			S-32A			S-32B			S-32C			S-32D			S-33A		
Sample ID				460-11823-49			460-11823-50			460-11823-51			460-11823-52			460-11823-53			460-11823-54		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			1			1			1			1			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.019	0.097	U	0.019	0.10	U	0.020	0.11	U	0.020	0.10	U	0.020	0.11	U	0.018	0.095	U
Aroclor 1221	0.20	1.0	0.20	0.029	0.097	U	0.030	0.10	U	0.032	0.11	U	0.031	0.10	U	0.032	0.11	U	0.029	0.095	U
Aroclor 1232	0.20	1.0	0.20	0.055	0.097	U	0.057	0.10	U	0.060	0.11	U	0.059	0.10	U	0.060	0.11	U	0.054	0.095	U
Aroclor 1242	0.20	1.0	0.20	0.018	0.097	U	0.019	0.10	U	0.020	0.11	U	0.020	0.10	U	0.020	0.11	U	0.018	0.095	U
Aroclor 1248	0.20	1.0	0.20	0.026	0.058	J	0.027	0.10	U	0.028	0.11	U	0.027	0.10	U	0.028	0.11	U	0.025	0.095	U
Aroclor 1254	0.20	1.0	0.20	0.033	0.097	U	0.034	0.19		0.036	0.21		0.035	0.20		0.036	0.31		0.032	1.3	
Aroclor 1260	0.20	1.0	0.20	0.011	0.097	U	0.011	0.10	U	0.012	0.11	U	0.012	0.10	U	0.012	0.11	U	0.011	0.095	U
Aroclor 1262	NA	NA	NA	0.017	0.097	U	0.017	0.10	U	0.018	0.11	U	0.018	0.10	U	0.018	0.11	U	0.016	0.095	U
Aroclor 1268	NA	NA	NA	0.017	0.097	U	0.017	0.10	U	0.018	0.11	U	0.018	0.10	U	0.018	0.11	U	0.016	0.095	U
Percent Solids (%)	NA	NA	NA	1.0	68.9		1.0	67.0		1.0	63.3		1.0	64.9		1.0	63.5		1.0	70.7	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceednce of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-33B			S-33C			S-33D			S-36A			S-36B			S-36C		
Sample ID				460-11823-55			460-11823-56			460-11823-57			460-11823-58			460-11823-59			460-11823-60		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			5			1			1			5			1		
Parameter (mg/kg)																					
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.022	0.11	U	0.10	0.53	U	0.018	0.092	U	0.016	0.085	U	0.084	0.44	U	0.017	0.087	U
Aroclor 1221	0.20	1.0	0.20	0.034	0.11	U	0.16	0.53	U	0.028	0.092	U	0.026	0.085	U	0.13	0.44	U	0.026	0.087	U
Aroclor 1232	0.20	1.0	0.20	0.064	0.11	U	0.30	0.53	U	0.052	0.092	U	0.048	0.085	U	0.25	0.44	U	0.050	0.087	U
Aroclor 1242	0.20	1.0	0.20	0.021	0.11	U	0.10	0.53	U	0.017	0.092	U	0.016	0.085	U	0.083	0.44	U	0.017	0.087	U
Aroclor 1248	0.20	1.0	0.20	0.030	0.11	U	0.14	8.7	U	0.024	0.092	U	0.023	0.085	U	0.12	4.5	U	0.023	0.087	U
Aroclor 1254	0.20	1.0	0.20	0.038	0.41	U	0.18	0.53	U	0.031	1.1	U	0.029	0.44	U	0.15	0.44	U	0.030	1.3	U
Aroclor 1260	0.20	1.0	0.20	0.013	0.11	U	0.059	0.53	U	0.010	0.092	U	0.0095	0.085	U	0.049	0.44	U	0.0098	0.087	U
Aroclor 1262	NA	NA	NA	0.019	0.11	U	0.090	0.53	U	0.016	0.092	U	0.015	0.085	U	0.075	0.44	U	0.015	0.087	U
Aroclor 1268	NA	NA	NA	0.019	0.11	U	0.090	0.53	U	0.016	0.092	U	0.015	0.085	U	0.075	0.44	U	0.015	0.087	U
Percent Solids (%)	NA	NA	NA	1.0	59.4		1.0	63.6		1.0	72.9		1.0	78.4		1.0	76.1		1.0	76.4	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 6: April 1, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	S-36D			D-1			D-2			D-3			D-4		
Sample ID				460-11823-61			460-11823-62			460-11823-63			460-11823-64			460-11823-65		
Sample Date				4/1/10			4/1/10			4/1/10			4/1/10			4/1/10		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil		
Dilution Factor				1			1			5			1			1		
Parameter (mg/kg)																		
PCBs				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
Aroclor 1016	0.20	1.0	0.20	0.016	0.086	U	0.021	0.11	U	0.10	0.55	U	0.020	0.11	U	0.018	0.096	U
Aroclor 1221	0.20	1.0	0.20	0.026	0.086	U	0.032	0.11	U	0.17	0.55	U	0.032	0.11	U	0.029	0.096	U
Aroclor 1232	0.20	1.0	0.20	0.049	0.086	U	0.061	0.11	U	0.31	0.55	U	0.061	0.11	U	0.055	0.096	U
Aroclor 1242	0.20	1.0	0.20	0.016	0.086	U	0.020	0.11	U	0.10	0.55	U	0.020	0.11	U	0.018	0.096	U
Aroclor 1248	0.20	1.0	0.20	0.023	0.086	U	0.029	0.11	U	0.15	4.3		0.029	0.11	U	0.026	0.096	U
Aroclor 1254	0.20	1.0	0.20	0.029	0.46		0.037	0.11	U	0.19	0.55	U	0.037	0.15		0.033	0.096	U
Aroclor 1260	0.20	1.0	0.20	0.0096	0.086	U	0.012	0.11	U	0.061	0.55	U	0.012	0.11	U	0.011	0.096	U
Aroclor 1262	NA	NA	NA	0.015	0.086	U	0.018	0.11	U	0.094	0.55	U	0.018	0.11	U	0.017	0.096	U
Aroclor 1268	NA	NA	NA	0.015	0.086	U	0.018	0.11	U	0.094	0.55	U	0.018	0.11	U	0.017	0.096	U
Percent Solids (%)	NA	NA	NA	1.0	77.5		1.0	62.3		1.0	60.8		1.0	62.4		1.0	69.4	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

U: Indicates the analyte was analyzed for but not detected.

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 7: January 3, 2011 Remedial Investigation Summary of Analytical Results
Braddock Frosted Foods
Braddock Avenue and Bailey Lane
Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-1			SB-2			SB-3			SB-4			SB-5			SB-6			SB-7			SB-8											
Sample ID				460-21723-1			460-21723-2			460-21723-3			460-21723-4			460-21723-5			460-21723-6			460-21723-7			460-21723-8											
Sample Date				1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011											
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'											
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil			Soil			Soil											
				1			1			1			1			1			1			1			1											
Parameter (mg/kg)	MDL			Result			Q			MDL			Result			Q			MDL			Result			Q			MDL			Result			Q		
PCBs																																				
Aroclor 1016	0.20	1.0	0.20	0.018	0.092	U	0.018	0.092	U	0.017	0.089	U	0.018	0.094	U	0.018	0.094	U	0.019	0.10	U	0.016	0.083	U	0.014	0.075	U									
Aroclor 1221	0.20	1.0	0.20	0.028	0.092	U	0.028	0.092	U	0.027	0.089	U	0.028	0.094	U	0.028	0.094	U	0.030	0.10	U	0.025	0.083	U	0.023	0.075	U									
Aroclor 1232	0.20	1.0	0.20	0.052	0.092	U	0.052	0.092	U	0.051	0.089	U	0.053	0.094	U	0.053	0.094	U	0.057	0.10	U	0.047	0.083	U	0.042	0.075	U									
Aroclor 1242	0.20	1.0	0.20	0.018	0.092	U	0.018	0.092	U	0.017	0.089	U	0.018	0.094	U	0.018	0.094	U	0.019	0.10	U	0.016	0.083	U	0.014	0.075	U									
Aroclor 1248	0.20	1.0	0.20	0.025	1.3		0.025	0.092	U	0.024	0.96		0.025	1.4		0.025	0.85		0.027	1.0		0.022	0.083	U	0.020	0.075	U									
Aroclor 1254	0.20	1.0	0.20	0.032	0.092	U	0.032	0.54		0.031	0.089	U	0.032	0.094	U	0.032	0.094	U	0.034	0.10	U	0.029	0.083	U	0.026	0.075	U									
Aroclor 1260	0.20	1.0	0.20	0.010	0.092	U *	0.010	0.092	U *	0.010	0.089	U *	0.010	0.094	U *	0.011	0.094	U *	0.011	0.10	U *	0.0093	0.083	U *	0.0084	0.075	U *									
Aroclor 1262	NA	NA	NA	0.016	0.092	U	0.016	0.092	U	0.015	0.089	U	0.016	0.094	U	0.016	0.094	U	0.017	0.10	U	0.014	0.083	U	0.013	0.075	U									
Aroclor 1268	NA	NA	NA	0.016	0.092	U	0.016	0.092	U	0.015	0.089	U	0.016	0.094	U	0.016	0.094	U	0.017	0.10	U	0.014	0.083	U	0.013	0.075	U									
Percent Solids (%)	NA	NA	NA	1.0	72.4		1.0	88.7		1.0	84.4		1.0	86.3		1.0	74.8		1.0	71.9		1.0	66.3		1.0	71.1										

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

*: Recovery or RPD exceeds control limits

J: Result is less than the RL but greater than or equal to the MDL.

The concentration is an approximate value.

U: Indicates the analyte was analyzed for but not detected.

Q: Qualifier

MDL: Method Detection Limit

Red Highlight Indicates an Exceednce of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 7: January 3, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-9			SB-10			SB-11			SB-12			SB-13			SB-14			SB-15			SB-16		
Sample ID				460-21723-9			460-21723-10			460-21723-11			460-21723-12			460-21723-13			460-21723-14			460-21723-15			460-21723-16		
Sample Date				1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil			Soil			Soil		
				1			1			1			1			1			1			5			1		
Parameter (mg/kg)				MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
PCBs																											
Aroclor 1016	0.20	1.0	0.20	0.014	0.074	U	0.014	0.075	U	0.015	0.079	U	0.015	0.078	U	0.017	0.089	U	0.018	0.093	U	0.096	0.50	U	0.018	0.094	U
Aroclor 1221	0.20	1.0	0.20	0.022	0.074	U	0.023	0.075	U	0.024	0.079	U	0.023	0.078	U	0.027	0.089	U	0.028	0.093	U	0.15	0.50	U	0.028	0.094	U
Aroclor 1232	0.20	1.0	0.20	0.042	0.074	U	0.043	0.075	U	0.045	0.079	U	0.044	0.078	U	0.051	0.089	U	0.053	0.093	U	0.29	0.50	U	0.053	0.094	U
Aroclor 1242	0.20	1.0	0.20	0.014	0.074	U	0.014	0.075	U	0.015	0.079	U	0.015	0.078	U	0.017	0.089	U	0.018	0.093	U	0.095	0.50	U	0.018	0.094	U
Aroclor 1248	0.20	1.0	0.20	0.020	0.074	U	0.020	0.075	U	0.021	0.079	U	0.021	0.078	U	0.024	0.089	U	0.025	0.093	U	0.13	5.2		0.025	0.094	U
Aroclor 1254	0.20	1.0	0.20	0.025	0.074	U	0.026	0.075	U	0.027	1.1		0.027	0.078	U	0.031	0.38		0.032	1.8		0.17	0.50	U	0.032	0.69	
Aroclor 1260	0.20	1.0	0.20	0.0083	0.074	U	0.0084	0.075	U	0.0088	0.079	U	0.0087	0.078	U	0.010	0.089	U	0.010	0.093	U	0.056	0.50	U	0.011	0.094	U
Aroclor 1262	NA	NA	NA	0.013	0.074	U	0.013	0.075	U	0.014	0.079	U	0.013	0.078	U	0.015	0.089	U	0.016	0.093	U	0.086	0.50	U	0.016	0.094	U
Aroclor 1268	NA	NA	NA	0.013	0.074	U	0.013	0.075	U	0.014	0.079	U	0.013	0.078	U	0.015	0.089	U	0.016	0.093	U	0.086	0.50	U	0.016	0.094	U
Percent Solids (%)	NA	NA	NA	1.0	80.0		1.0	71.2		1.0	75.7		1.0	72.3		1.0	68.7		1.0	56.7		1.0	87.5		1.0	79.6	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

*: Recovery or RPD exceeds control limits

J: Result is less than the RL but greater than or equal to the MDL.

The concentration is an approximate value.

U: Indicates the analyte was analyzed for but not detected.

Q: Qualifier

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 7: January 3, 2011 Remedial Investigation Summary of Analytical Results
Braddock Frosted Foods
Braddock Avenue and Bailey Lane
Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-17			SB-18			SB-19			SB-20			SB-21			SB-22			SB-23			SB-24		
Sample ID				460-21723-17			460-21723-18			460-21723-19			460-21723-20			460-21723-21			460-21723-22			460-21723-23			460-21723-24		
Sample Date				1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil			Soil			Soil		
				1			1			1			1			1			1			1			1		
Parameter (mg/kg)	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
PCBs																											
Aroclor 1016	0.20	1.0	0.20	0.016	0.084	U	0.018	0.094	U	0.017	0.089	U	0.019	0.097	U	0.023	0.12	U	0.015	0.076	U	0.016	0.084	U	0.015	0.077	U
Aroclor 1221	0.20	1.0	0.20	0.025	0.084	U	0.028	0.094	U	0.027	0.089	U	0.029	0.097	U	0.036	0.12	U	0.023	0.076	U	0.025	0.084	U	0.023	0.077	U
Aroclor 1232	0.20	1.0	0.20	0.047	0.084	U	0.053	0.094	U	0.050	0.089	U	0.055	0.097	U	0.067	0.12	U	0.043	0.076	U	0.048	0.084	U	0.044	0.077	U
Aroclor 1242	0.20	1.0	0.20	0.016	0.084	U	0.018	0.094	U	0.017	0.089	U	0.018	0.097	U	0.022	0.12	U	0.014	0.076	U	0.016	0.084	U	0.015	0.077	U
Aroclor 1248	0.20	1.0	0.20	0.022	0.084	U	0.025	1.2		0.024	0.089	U	0.026	0.46		0.031	0.12	U	0.020	0.076	U	0.022	0.084	U	0.021	0.077	U
Aroclor 1254	0.20	1.0	0.20	0.029	0.20		0.032	0.094	U	0.030	0.089	U	0.033	0.097	U	0.040	0.12	U	0.026	0.076	U	0.029	0.084	U	0.026	0.077	U
Aroclor 1260	0.20	1.0	0.20	0.0093	0.084	U	0.011	0.094	U	0.0099	0.089	U	0.011	0.097	U	0.013	0.12	U	0.0085	0.076	U	0.0094	0.084	U	0.0086	0.077	U
Aroclor 1262	NA	NA	NA	0.014	0.084	U	0.016	0.094	U	0.015	0.089	U	0.017	0.097	U	0.020	0.12	U	0.013	0.076	U	0.014	0.084	U	0.013	0.077	U
Aroclor 1268	NA	NA	NA	0.014	0.084	U	0.016	0.094	U	0.015	0.089	U	0.017	0.097	U	0.020	0.12	U	0.013	0.076	U	0.014	0.084	U	0.013	0.077	U
Percent Solids (%)	NA	NA	NA	1.0	86.8		1.0	91.4		1.0	81.9		1.0	72.9		1.0	80.8		1.0	78.0		1.0	74.7		1.0	73.2	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

*: Recovery or RPD exceeds control limits

J: Result is less than the RL but greater than or equal to the MDL.

The concentration is an approximate value.

U: Indicates the analyte was analyzed for but not detected.

Q: Qualifier

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 7: January 3, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-25			SB-26			SB-27			SB-28			SB-29			SB-30			SB-31			SB-32		
Sample ID				460-21723-25			460-21723-26			460-21723-27			460-21723-28			460-21723-29			460-21723-30			460-21723-31			460-21723-32		
Sample Date				1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011			1/3/2011		
Sample Depth				0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil			Soil			Soil			Soil			Soil			Soil			Soil		
	1			1			1			1			1			1			1			1					
Parameter (mg/kg)	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q	MDL	Result	Q
PCBs																											
Aroclor 1016	0.20	1.0	0.20	0.014	0.073	U	0.016	0.082	U	0.018	0.092	U	0.016	0.083	U	0.016	0.086	U	0.018	0.092	U	0.049	0.26	U	0.015	0.079	U
Aroclor 1221	0.20	1.0	0.20	0.022	0.073	U	0.025	0.082	U	0.028	0.092	U	0.025	0.083	U	0.026	0.086	U	0.028	0.092	U	0.078	0.26	U	0.024	0.079	U
Aroclor 1232	0.20	1.0	0.20	0.041	0.073	U	0.046	0.082	U	0.052	0.092	U	0.047	0.083	U	0.049	0.086	U	0.052	0.092	U	0.15	0.26	U	0.045	0.079	U
Aroclor 1242	0.20	1.0	0.20	0.014	0.073	U	0.015	0.082	U	0.017	0.092	U	0.016	0.083	U	0.016	0.086	U	0.017	0.092	U	0.049	0.26	U	0.015	0.079	U
Aroclor 1248	0.20	1.0	0.20	0.019	0.073	U	0.022	0.046	J	0.024	0.092	U	0.022	0.34		0.023	0.086	U	0.024	0.092	U	0.068	0.26	U	0.021	0.079	U
Aroclor 1254	0.20	1.0	0.20	0.025	0.073	U	0.028	0.082	U	0.031	0.092	U	0.028	0.083	U	0.029	0.086	U	0.031	0.092	U	0.088	0.26	U	0.027	0.079	U
Aroclor 1260	0.20	1.0	0.20	0.0082	0.073	U	0.0091	0.082	U	0.010	0.092	U	0.0093	0.083	U	0.0096	0.086	U	0.010	0.092	U	0.029	0.26	U	0.0088	0.079	U
Aroclor 1262	NA	NA	NA	0.013	0.073	U	0.014	0.082	U	0.016	0.092	U	0.014	0.083	U	0.015	0.086	U	0.016	0.092	U	0.044	0.26	U	0.014	0.079	U
Aroclor 1268	NA	NA	NA	0.013	0.073	U	0.014	0.082	U	0.016	0.092	U	0.014	0.083	U	0.015	0.086	U	0.016	0.092	U	0.044	0.26	U	0.014	0.079	U
Percent Solids (%)	NA	NA	NA	1.0	26.1		1.0	85.2		1.0	73.2		1.0	77.1		1.0	71.2		1.0	71.0		1.0	66.7		1.0	80.3	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

*: Recovery or RPD exceeds control limits

J: Result is less than the RL but greater than or equal to the MDL.

The concentration is an approximate value.

U: Indicates the analyte was analyzed for but not detected.

Q: Qualifier

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 7: January 3, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-33			SB-34		
Sample ID				460-21723-33			460-21723-34		
Sample Date				1/3/2011			1/3/2011		
Sample Depth				0.0-0.5'			0.0-0.5'		
Sample Matrix				Soil			Soil		
				1			1		
Parameter (mg/kg)				MDL	Result	Q	MDL	Result	Q
PCBs									
Aroclor 1016	0.20	1.0	0.20	0.018	0.092	U	0.017	0.087	U
Aroclor 1221	0.20	1.0	0.20	0.028	0.092	U	0.026	0.087	U
Aroclor 1232	0.20	1.0	0.20	0.052	0.092	U	0.049	0.087	U
Aroclor 1242	0.20	1.0	0.20	0.017	0.092	U	0.016	0.087	U
Aroclor 1248	0.20	1.0	0.20	0.024	0.092	U	0.023	0.087	U
Aroclor 1254	0.20	1.0	0.20	0.031	0.092	U	0.030	0.087	U
Aroclor 1260	0.20	1.0	0.20	0.010	0.092	U	0.0097	0.087	U
Aroclor 1262	NA	NA	NA	0.016	0.092	U	0.015	0.087	U
Aroclor 1268	NA	NA	NA	0.016	0.092	U	0.015	0.087	U
Percent Solids (%)	NA	NA	NA	1.0	89.2		1.0	90.0	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

*: Recovery or RPD exceeds control limits

J: Result is less than the RL but greater than or equal to the MDL.

The concentration is an approximate value.

U: Indicates the analyte was analyzed for but not detected.

Q: Qualifier

MDL: Method Detection Limit

Red Highlight Indicates an Exceedence of the Applicable Standard

Grey Highlight Indicates a MDL Exceeds the Applicable Standard

Table 8: February 16, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-41		SB-42		SB-43		SB-44		SB-45		SB-46		SB-47		SB-48		SB-49		SB-50	
Sample ID				AC57327-007		AC57327-008		AC57327-009		AC57327-010		AC57327-011		AC57327-012		AC57327-013		AC57327-014		AC57327-015		AC57327-016	
Sample Date				2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011	
Sample Depth				0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'	
Sample Matrix				Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil		Soil	
Parameter (mg/kg)				Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBs																							
Aroclor (Total)	0.2	1	NA	0.097	0.034	ND	0.03	ND	0.031	0.12	0.037	0.15	0.034	0.67	0.036	1.4	0.036	0.56	0.031	0.43	0.033	ND	0.036
Aroclor-1016	0.2	1	0.2	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1221	0.2	1	0.2	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1232	0.2	1	0.2	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1242	0.2	1	0.2	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1248	0.2	1	0.2	0.097	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1254	0.2	1	0.2	ND	0.034	ND	0.03	ND	0.031	0.12	0.037	0.15	0.034	ND	0.036	1.2	0.036	0.56	0.031	0.43	0.033	ND	0.036
Aroclor-1260	0.2	1	0.2	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1262	NA	NA	NA	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	0.18	0.036	ND	0.031	ND	0.033	ND	0.036
Aroclor-1268	NA	NA	NA	ND	0.034	ND	0.03	ND	0.031	ND	0.037	ND	0.034	ND	0.036	ND	0.036	ND	0.031	ND	0.033	ND	0.036
Wet Chemistry																							
% Solids	NA	NA	NA	73		84		80		67		73		70		70		80		76		69	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 8: February 16, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-54		SB-55		SB-56		SB-59		SB-59a		SB-60		SB-61		SB-61a		SB-62		SB-63		
Sample ID				AC57327-020		AC57327-021		AC57327-022		AC57327-025		AC57327-026		AC57327-027		AC57327-029		AC57327-030		AC57327-031		AC57327-033		
Sample Date				2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		
Sample Depth				Soil		0.0-0.5'		Soil		1.5-2.0'		2.5-3.0'		1.5-2.0'		1.5-2.0'		2.5-3.0'		1.5-2.0'		1.5-2.0'		
Sample Matrix				mg/Kg		Soil		mg/Kg		Soil		Soil		Soil		Soil		Soil		Soil		Soil		
Parameter (mg/kg)	Result		RL		Result		RL		Result		RL		Result		RL		Result		RL		Result		RL	
PCBs																								
Aroclor (Total)	0.2	1	NA	12	0.68	2.6	0.19	0.31	0.031	3.9	0.15	0.92	0.031	ND	0.029	16	0.6	ND	0.03	ND	0.028	3	0.16	
Aroclor-1016	0.2	1	0.2	ND	0.68	ND	0.19	ND	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1221	0.2	1	0.2	ND	0.68	ND	0.19	ND	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1232	0.2	1	0.2	ND	0.68	ND	0.19	ND	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1242	0.2	1	0.2	ND	0.68	ND	0.19	ND	0.031	ND	0.15	0.92	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1248	0.2	1	0.2	ND	0.68	ND	0.19	ND	0.031	3.9	0.15	ND	0.031	ND	0.029	16	0.6	ND	0.03	ND	0.028	3	0.16	
Aroclor-1254	0.2	1	0.2	12	0.68	2.6	0.19	0.31	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1260	0.2	1	0.2	ND	0.68	ND	0.19	ND	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1262	NA	NA	NA	ND	0.68	ND	0.19	ND	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Aroclor-1268	NA	NA	NA	ND	0.68	ND	0.19	ND	0.031	ND	0.15	ND	0.031	ND	0.029	ND	0.6	ND	0.03	ND	0.028	ND	0.16	
Wet Chemistry																								
% Solids	NA	NA	NA	73		67		80		85		80		87		83		84		90		80		

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceedence of the Applicable Standard

Table 8: February 16, 2011 Remedial Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RDC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-63a		SB-64	
Sample ID				AC57327-034		AC57327-035	
Sample Date				2/16/2011		2/16/2011	
Sample Depth				2.5-3.0'		1.5-2.0'	
Sample Matrix				Soil		Soil	
Parameter (mg/kg)				Result	RL	Result	RL
PCBs							
Aroclor (Total)	0.2	1	NA	2.9	0.15	ND	0.029
Aroclor-1016	0.2	1	0.2	ND	0.15	ND	0.029
Aroclor-1221	0.2	1	0.2	ND	0.15	ND	0.029
Aroclor-1232	0.2	1	0.2	ND	0.15	ND	0.029
Aroclor-1242	0.2	1	0.2	ND	0.15	ND	0.029
Aroclor-1248	0.2	1	0.2	2.9	0.15	ND	0.029
Aroclor-1254	0.2	1	0.2	ND	0.15	ND	0.029
Aroclor-1260	0.2	1	0.2	ND	0.15	ND	0.029
Aroclor-1262	NA	NA	NA	ND	0.15	ND	0.029
Aroclor-1268	NA	NA	NA	ND	0.15	ND	0.029
Wet Chemistry							
% Solids	NA	NA	NA	86		86	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceednce of the Applicable Standard

Table 9: February 16, 2011 Impact to Ground Water Investigation Investigation Summary of Analytical Results
 Braddock Frosted Foods
 Braddock Avenue and Bailey Lane
 Winslow Township, Camden County, New Jersey

Client ID	NJDEP RSC SRS	NJDEP NRDC SRS	NJDEP IGW SSL	SB-35		SB-36		SB-37		SB-38		SB-39		SB-40	
Sample ID				AC57327-001		AC57327-002		AC57327-003		AC57327-004		AC57327-005		AC57327-006	
Sample Date				2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011		2/16/2011	
Sample Depth				0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'		0.0-0.5'	
Sample Matrix				Soil		Soil		Soil		Soil		Soil		Soil	
Parameter	mg/Kg	mg/Kg	mg/Kg	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL	Result	RL
PCBs-Soil (mg/kg)															
Aroclor (Total)	0.2	1	NA	4.6	0.16	160	4.2	6.9	0.19	6.4	0.16	5.7	0.16	0.41	0.03
Aroclor-1016	0.2	1	0.2	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Aroclor-1221	0.2	1	0.2	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Aroclor-1232	0.2	1	0.2	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Aroclor-1242	0.2	1	0.2	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Aroclor-1248	0.2	1	0.2	ND	0.16	160	4.2	6.9	0.19	6.4	0.16	5.7	0.16	ND	0.03
Aroclor-1254	0.2	1	0.2	4.6	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	0.41	0.03
Aroclor-1260	0.2	1	0.2	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Aroclor-1262	NA	NA	NA	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Aroclor-1268	NA	NA	NA	ND	0.16	ND	4.2	ND	0.19	ND	0.16	ND	0.16	ND	0.03
Wet Chemistry															
% Solids	NA	NA	NA	79		60		67		78		79		84	

NJDEP - New Jersey Department of Environmental Protection

RDC SRS - Residential Direct Contact Soil Remediation Standard

NRDC SRS - Non-Residential Direct Contact Soil Remediation Standard

IGW SSL - Impact to Ground Water Soil Screening Level

NA - No Standard

ND: Indicates the analyte was analyzed for but not detected.

RL: Reporting Limit

Highlight Indicates an Exceednce of the Applicable Standard


CERTIFICATION

On behalf of Braddock Frosted Foods, Inc., the owner of the property where the cleanup site is located and the party conducting the cleanup, the undersigned hereby certifies that all sampling plans, sample collection procedures, sample preparation procedures, extraction procedures, and instrumental/chemical analysis procedures used to assess or characterize the PCB contamination at the cleanup site, are on file at the location indicated below and are available for EPA inspection.

Document Location

Northstar Environmental Services
36 Clermont Drive, Clermont, NJ 08210

Property Owner and Party Conducting the Cleanup:
Braddock Frosted Foods, Inc.



Mr. Francis Keenan
Vice President
Braddock Frosted Foods, Inc.
P.O. Box 305
Fort Washington, PA 19034

Date: 2/15/12

